


**U.P. State Construction and Infrastructure Development Corporation  
Ltd. Meerut**

*Name of work :— Repair and Maintenance of existing Boundary wall at R.T.O  
office Campus Meerut*

**Bill of Quantity**

| S. N.    | Particulars  | Qty.    | Unit           | Rate    | Amount    |
|----------|--|---------|----------------|---------|-----------|
| <b>A</b> | <b>Raising of Boundary wall :-</b>   |         |                |         |           |
| 1        | 230mm thick brick work in 1:6 C:C/Sand mortar in superstructure 303+Cement Diff. +309+310/2015 | 95.19   | M <sup>3</sup> | 4230.00 | 402653.70 |
| 2        | 12mm thick plaster in 1:4 C:C/Sand mortar S.I. No. 584a/2015                                   | 445.50  | M <sup>2</sup> | 135.00  | 60142.50  |
| 3        | 15mm thick plaster in 1:4 C:C/Sand mortar S.I. No. 584a+596/2015                               | 577.27  | M <sup>2</sup> | 147.00  | 84858.69  |
| 4        | C.C 1:2:4 C:C/S: S/G top over boundary S.I. No. 279a/2015                                      | 5.24    | M <sup>3</sup> | 5150.00 | 26986.00  |
| 5        | Providing kanch chips on top over boundary to safty purpose M.R                                | 104.74  | M <sup>2</sup> | 30.00   | 3142.20   |
| 6        | Colour washing two coat on previously painted surface S.I. No. 675/2015                        | 683.10  | M <sup>2</sup> | 16.00   | 10929.60  |
| 7        | Colour washing two coat on New plaster surface with one coat of base coat S.I. No. 671+675     | 1022.77 | M <sup>2</sup> | 23.00   | 23523.71  |
| 8        | Dismantiling of existing squre pipe MS railing S.I. No. 704/2015                               | 128.52  | M <sup>2</sup> | 20.00   | 2570.40   |
| <b>B</b> | <b>MS Boundary wall gate with R.C.C pillar :-</b>  |         |                |         | 0.00      |
| 1        | Earth work excecavation in foundation S.I. No. 251a/2015                                       | 6.50    | M <sup>3</sup> | 63.00   | 409.50    |
| 2        | Lean concrete in 1:4:8 C:F/S: B ballast 40mm S.I. No. 275/2015                                 | 0.65    | M <sup>3</sup> | 2500.00 | 1625.00   |
| 3        | R.C.C work in 1:1.5:3 C:C/S: S/grit S.I. No. 284a  | 5.08    | M <sup>3</sup> | 6700.00 | 34036.00  |
| 4        | Steel Reinforcement in R.C.C work S.I. No. 504/2015  | 398.78  | Kg.            | 59.00   | 23528.02  |
| 5        | 10mm plaster in 1:3 C:C/S mortar on R.C.C work S.I. No. 582a+587                               | 23.44   | M <sup>2</sup> | 152.00  | 3562.88   |

  
 श्री. अशोक सिंह  
 प्रमुख अभियंता  
 प्रकल्प एवं इन्फ्रास्ट्रक्चर  
 विभाग, उत्तर प्रदेश विकास नि. बंगलूर

|   |  |        |                |                  |                  |
|---|--|--------|----------------|------------------|------------------|
| 6 | Colour washing two coat on New plaster surface with one coat of base coat S.I. No. 671+675 | 23.44  | M <sup>2</sup> | 23.00            | 539.12           |
| 7 | Providing and fixing MS gate   | 940.80 | Kg.            | 90.00            | 84672.00         |
| 8 | Enamel painting two coat on MS gate S.I. No. 641+642/2015                                  | 26.88  | M <sup>2</sup> | 81.00            | 2177.28          |
|   |  |        |                | <b>Total Rs.</b> | <b>765356.60</b> |

Say Rs. 7.65 Lac

ई० सत्यनर सिंह  
 सहायक अभियन्ता  
 यू०पी० स्टेट कॉन्स्ट्रक्शन एंड इन्फ्रास्ट्रक्चर  
 डेवलपमेंट कॉर्पोरेशन लि० नारायण

0